

19-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- McKNAB & LINDSAY
Farm- Kuhn-Devlin No. 8

SEC. 19 T. 26 R. 34W
C 1/4 NW

Total Depth. 5153'
Comm. 10-2-58 Comp. 10-23-58
Shot or Treated.
Contractor. McKnab & Lindsay
Issued. 3-21-59

County Finney
KANSAS



Elevation. 2982' RB

CASING:

8 5/8" 805' cem w/425 sx.
5 1/2" 5152' cem w/250 sx.

1 D V tool at 2797 and 1 basket 200 sks cement @ 2797 Production. 150 BOPD
Figures indicate Bottom of Formations.

sand	360
shale, sand & shells	650
shale & lime	775
red bed	805
red bed & sand	1340
red bed, sand & gyp	1540
red bed, gyp, salt & sand	1705
shale	1875
lime & shale	2595
lime	2780
lime, shale & chalk	2880
lime	3667
lime & chalk	3790
lime	4828
lime & shale	4866
lime, shale & sand	4950
shale & lime	4958
lime	5153
Total Depth	

TOPS:

Topeka	3421
Heebner	3833
Toronto	3857
Lansing	3890
Marmaton	4451
Atoka	4814
Morrow	4875
Mississippi	4956
St. Louis	5027