


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- E. Brown No. 1

SEC. 20 T. 26 R. 34W
C SW SW

Total Depth. 5203'
Comm. 11-3-58 Comp. 1-20-59
Shot or Treated.
Contractor. General Drlg. Co.
Issued. 3-7-59

County Finney
KANSAS



CASING:

8 5/8" 814' cem w/525 sx.
5 1/2" 5199' cem w/975 sx.

Elevation. 2997'

Production. 170 BOPD, NW

Figures Indicate Bottom of Formations.

sand	384
sand & gyp	1325
redbed, sand & shale	1908
shale & lime	3208
lime & chalk	3280
lime, shale & chalk	4054
lime	4135
lime & chalk	4273
lime, shale w/chalk	4481
lime, shale & sand	4730
lime & shale	4841
lime	5085
lime & shale	5157
lime & sand	5203
Total Depth	

TOPS:

Winfield	2610
Heebner	3898
Lansing	3944
Marmaton	4513
Cherokee	4664
Atoka	4868
Morrow	4928
St. Genevieve	4998
St. Louis	5054

PERFORATIONS:

Perf. 5134-47 w/52 sh. Swab 9 BO NW/3 hrs.
Acidized w/2000 gals. reg. acid
Vac. all the way. Overflush w/85
BLW Swab 85 BLW/3 hrs. Minus 48
BAW