

20-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- MOBIL OIL COMPANY
Farm- C. L. Reeve No. 4

SEC. 20 T. 26S R. 34W
C NE NE

Total Depth. 5170'
Comm. 10-27-59 Comp. 11-24-59
Shot or Treated.
Contractor. Tommy Ward Drilling Co.
issued. 4-23-60

County Finney
KANSAS



Elevation. 2952

Production. 245 BOPD

CASING:

8 5/8" 833' w/480 sks.
5 1/2" 5168' w/DV tool @ 2807', Cem.
1st stage w/375 sks, 2nd stage
2/700 sks. Figures indicate Bottom of Formations.

- sand 635
- sand, shale, anhydrite 845
- sand, shale 1120
- red bed sand 1925
- anhydrite, shale 2065
- lime 2322
- lime, shale 2465
- lime 2720
- lime, shale 3130
- lime 4046
- lime, chalk, shale 4150
- lime 5170
- Total Depth

TOPS: SCOUT
Morrison 4877
Mississippi 4953

TOPS:
Kansas City 3886
St. Louis 5030

○ Perf. 5117023' w/24" jet holes. Acidized w/1000 gal 15% acid. Acidized w/2000 gal 15% acid.

Perf. 5082-96' & 5054-66' w/104 1/2" jet holes. Acidized w/2000 gal 15% acid. Acid Frac w/15,000# sand & 15,000 gal Gell acid

Perf. 5032-40 w/32 1/2" jet holes. Acidized w/1000 gal 15% acid.

Perf. 5004-10', 4986-92' w/72 1/2" jet holes Acidized w/2000 gal 15% acid. Acid Frac w/10,000# sand & 10,000 gal acid.