


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
 Farm- C. L. Reeve No. 1

SEC. 20 T. 26 R. 34W
 C SW NW

Total Depth. 5220'
 Comm. 9-24-58 Comp. 11-10-58
 Shot or Treated.
 Contractor. General Drilling Co.
 Issued. 2-7-59

County Finney
 KANSAS



CASING:

8 5/8" 815' cem w/515 sx.
 5 1/2" 5219' cdm w/1050 sx.

Elevation. 3000'

Production. 253 BOPD

Figures indicate Bottom of Formations.

sand	40
sand & shale	805
red bed	1900
shale & shells	2255
lime	2320
lime & shale	2425
shale, lime, salt & sand	2515
lime & shale	2572
lime	2627
sand & lime	2703
lime & shale	2776
lime	2835
sand, lime & shale	2880
lime & shale	3147
lime, shale, chalk	3479
lime & shale	3676
lime, shale & chalk	3954
lime & shale	4176
lime & gypsum	4240
lime, shale, chalk	4269
lime, shale & sand	4332
lime, shale & chalk	4406
lime & shale	4475
lime	4599
lime & shale	4969
lime, sand & shale	5189
lime & sand	5220
Total Depth	

TOPS:

Winfield (scout)	2605
Heebner	3888
Lansing	3936
Marmaton	4507
Cherokee	4655
Atoka	4863
Morrow	4923
St. Geneieve	5012
St. Louis	5068

PERFORATIONS:

#1 Perf. 5142-50 w/36 sh.
 Acidized w/1500 gals.