

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


20-26-34W

Company- MAGNOLIA PETROLEUM CO.
Farm- C. L. Reeve No. 3

SEC. 20 T. 26 R. 34W
C NE NW

Total Depth. 5185'
Comm. 5-1-59 Comp. 6-24-59
Shot or Treated.
Contractor. Tommy Ward Drlg.
Issued. 10-24-59

County Finney
KANSAS



CASING:

8 5/8" 846' cem w/840 sx.
5 1/2" 5179' cem w/225 sx.

Elevation. 2993'

Production. 262 BO & 7% Wtr.
24 hrs.

Figures indicate Bottom of Formations.

sand & shale	425
shale & anhydrite	847
shale	1033
red bed & shale	1892
shale	2375
shale & shells	2475
shale & lime	3583
chalky lime	3662
lime	3735
lime, chalk & shale	3865
lime & shale	3936
lime & chalk	3996
lime	4217
lime & chalk	4363
lime	4415
lime & shale	4685
lime	4877
lime & shale	5068
lime	5185
Total Depth	

TOPS:

Winfield	2580
Heebner	3852
Lansing-Kansas City	3899
Marmaton	4473
Cherokee	4616
Atoka	4825
Morrow	4886
St. Genevieve	4961
St. Louis	5033

PERFORATIONS:

5112-5115 w/12 shots
5121-5128 w/28 shots
5095-5100 w/20 shots
5034-5040 w/24 shots