

29-26-34W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas


Company - WHITE EAGLE OIL COMPANY
Farm - Jones No. 6

SEC. 29 T. 26 R. 34W
NE 1/4 SW
2310' NS1 & 2310' EWL SW 1/4

Total Depth. 2743'
Com m. 8-2-47
Shot or Treated, Acidized
Contractor.
Issued. 12-13-47

Comp. 9-2-47

County. Finney
KANSAS



Elevation. _____

CASING:

10-3/4" 774'
7" 2486'

Production. 3,906,000 Gas
R.P. 418.8 1/2

Figures Indicate Bottom of Formations.

sand & gravel 0-200
sand, gravel & clay 502
clay blue 615
sand & clay blue 750
red bed 1145
sand, shale & red bed 1600
sand & red bed , 1675
halo & shells 1950
shale, red bed & anhy-
drite 2200
anhydrite and shale 2490
anhydrite & limo 2495
limo RTD/ 2500
limo & shale 2530
limo 2620
shale 2638
limo 2675
lime & shale brks 2693
lime 2743
Total Depth

Tops:
Herrington 2529-2546
Kridor 2549-2568
Winfield 2581-2615
Upper Fort Riley 2650-2687
Lower Fort Riley 2702-2739
Florence 2739-2742

Acid. w/ 3000 gals., 15% acid.
" w/ 10,000 gals., 15% acid.
" w/ 4,000 gals., 7 1/2% acid.