

30-26-340

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY
Farm - Jones No. 5

SEC. 30 T. 26 R. 34W
SEc NW
330' NS1 & 2310' EW1 NW $\frac{1}{4}$

Total Depth. 2727'

Comm. 7-20-47

Comp. 7-27-47

Shot or Treated. Acidized

Contractor.

Issued. 12-13-47

County. Finney

KANSAS



Elevation. _____

CASING:

10-3/4" 779' Com. w/350 sx
7" 2552' Com. w/800 sx

Production. 20 mpa Open Flow
35,900 MCF Gas

Figures Indicate Bottom of Formations.

sand	0-140
sand & gravel	378
sand & clay	535
clay	650
chalky and clay	720
sand & clay blue	735
red bed	1160
red bed, sand & shale	1615
sand & shale	1885
shale, anhydrite shells	2060
shale, dolomite & red bed	2260
shale & sholls	2317
anhydrite & lime	2360
dolomite & shale	2445
lime brkn	2508
anhydrite & lime	2554
lime RTD	2576
lime	2607
shale blue	2610
shale brwn	2620
shale	2627
lime	2671
shale brwn	2690
lime	2727
Total Depth	

Tops:

Krider	2554-2564
Winfield	2571-2598
Upper Fort Riley	2639-2666
Lower Fort Riley	2683-2727

Acid. w/13,000, 15% acid.

" w/4,000, 7 $\frac{1}{2}$ % acid.