


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WHITE EAGLE OIL CO.
Farm- Devlin-Jones "B" No. 2

SEC. 30 T. 26 R. 34W
GSW NE

Total Depth. 6181'
Comm. 7-6-58 Comp. 7-31-58
Shot or Treated.
Contractor. Helmerich & Payne
Issued. 12-13-58

County Finney
KANSAS



Elevation. 3023' RB

Production. 158 BOPD

CASING:

10 3/4" 800' w/500 sx cem.
5 1/2" 5220' w/400 sx cem.

Figures Indicate Bottom of Formations.

sand, clay	164	Ste. Genevieve (Miss. lime)	4998
clay, shells	230	"A" Zone	5002 - Porosity & staining.
sand, clay	458	St. Louis	5042
sand	796	"B" Zone	5052 - " " "
red bed	816	"C" Zone	5102 - " " "
shale, red bed	1075	Spergen	5213
red bed	1580	Warsaw	5356
red bed, anhydrite	2128	Osage	5474
shale, Anhydrite	2500	Kinderhook	5682
lime, shale	3001	Viola	5776
lime, shale, chert	3086	Simpson	5925
lime, shale	5119	Arbuckle	5976
lime	5140		
lime, shale	5150		
lime	5166		
lime, shale	5229		
lime, shale, chert	5290		
lime	5313		
lime, chert	5370		
lime, shale	5476		
lime, shale, chert	5512		
cherty lime, shale	5518		
lime, shale	5547		
lime	5595		
lime, chert	5649		
cherty lime, shale	5688		
lime	5706		
cherty dolomite, lime	5767		
cherty lime, shale	5842		
lime	5991		
lime, shale	5996		
lime	6181		
Total Depth			

TOPS:	SCHL.
Topeka Lime	3450-Sample Top.
Heebner Shale	3869
Toronto Lime	3885
Lansing-Kansas City Lime	3913
B/Kansas City	4473
Marmaton	4498
Cherokee	4648
Atoka	4853
Morrow Shale	4914