

HELMERICH & PAYNE Inc.
Jones No. 1.

SEC 34 T. 26 R. 34W.
Center SE $\frac{1}{4}$


Total Depth. 2764
Comm. 6-16-36 Comp. 9-7-36
Shot or Treated.
Contractor.
Issued. 12-12-36

County Finney.

CASING.

10" 645' 7" 2509'

DEC 12 1936



Elevation.

Production. 3 1/4 McG.

Figures Indicate Bottom of Formations.

sand	630	lime grey	2600
shale,	775'	lime dark grey hard	2612
red bed.	1285	shale red and green	2625
sand	1295	lime grey	2630
red bed and lime	1430	lime light grey soft	2645
sand	1610	lime hard dark grey	2650
red bed	1860	shale green	2658
red rock and shells	1885	red rock	2670
anhydrite shale & red rock	1965	lime grey	2675
anhydrite shale and red bed	2030	shale green	2678
anhydrite & red rock	2040	lime brown	2680
red rock and gyp	2065	lime light grey	2690
red shale and gyp	2100	chat	2695
red rock and gyp	2190	lime dark grey hard	2700
shale red and anhydrite	2205	lime dark grey soft	2715
shale blue gyp and anhydrite	2300	gas increased 2705 looks like about	
anhydrite and shale	2335	half million.	
anhydrite and blue shale	2380	lime dark grey	2725
lime and chat	2405	soft 2718-2722	
sd lime	2420	gas a little stronger at 2720.	
anhydrite and shale	2455	lime dark grey sdy	2745
anhydrite shale and grey lime	2500	strong flow of gas 2740- 2745	
shale	2507	lime light grey	2747
dolomite	2515	lime very hard	2749
gyp lime	2520	soft gas pay	2755
shale red	2525	good gas increase 2755	
lime white	2530	lime white hard	2759
lime grey	2545	lime white	2762
shale green	2553	shale dark	2764
white glossy lime	2560	Total Depth.	
white glossy & grey lime			
mixed	2565		
lime grey	2570		
lime grey hardened at 2567 softened			
at 2570			
lime grey	2580		
lime dark grey hardened	2590		
shale dark	2595		