

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


32-26-34W

Company - WHITE EAGLE OIL COMPANY
Farm - Jones No. 4

SEC. 32 T. 26 R. 34W
SE 1/4 NW
330' NS1 & 2310' EW1 NW 1/4

Total Depth. 2764'
Comm. 8-14-47 Comp. 9-12-47
Shot or Treated. Acidized
Contractor.
Issued. 12-13-47

County. Finney
KANSAS



Elevation. _____

CASING:

10-3/4" 748' Com. w/350 sx
7" 2515' Com. w/800 sx

Production. Open Flow 3,582 MCF
Gas-72 hr. test

Figures Indicate Bottom of Formations.

sand	0-45
sand & gravel	495
sand & clay	621
shale red and sand rock	690
shale red	725
red bed	925
red bed & sand	1315
red bed & shale	1715
red bed, shale & shells	1926
red bed & anhydrite	2263
red bed, shale & anhydrite	2500
limo RTD	2523
limo	2620
shale	2638
limo & shale brks	2675
limo	2764
Total Depth	

Tops:

Horington	2364
Kridor	2574
Winfield	2618
Upper Ft. Riley	2680
Lower Ft. Riley	2716

Acidized w/ 3,000 gals., 15% acids
" w/10,000 gals.,