

32-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE, INC.
Farm- Jones No. O-34

SEC. 32 T. 26 R. 34W
CN $\frac{1}{2}$ SW SE
990' FSL 1980' FEL

Total Depth. 5215'
Comm. 11-22-59 Comp. 12-9-59
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 7-30-60

County Finney
KANSAS



Elevation. 2995' DF

Production. 30 BOED

CASING:

8 5/8" 823' w/350 sx cem.
5 1/2" 5215' w/

Figures Indicate Bottom of Formations.

sand	1189
sand, shale	1950
shale, anhydrite	2344
shale	2465
anhydrite, shale	2895
anhydrite	2966
lime, shale	3153
lime	3216
lime, shale	4216
lime	4290
lime, shale	4546
lime	4760
lime, shale	4830
cherty lime	4864
lime	4936
lime, shale	4975
lime	5112
sand, lime	5195
lime	5215
Total Depth	

TOES:

Topoka	3483
Heebner	3913
Toronto	3930
Lansing	3963
B/Kansas City	4519
Marmaton	4539
Cherokee	4696
Atoka	4912
Morrow	4976
Morrow sandstone	5066-5071
St. Louis	5091
"B" Zone	5092-5099
"C" "	5150-5160
"D" "	5190-5196