

32-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WHITE EAGLE OIL CO.
Farm- USA "A" No. 10

SEC. 32 T. 26 R. 34W
C SW NE

Total Depth. 5190'
Comm. 6-22-59 Comp. 7-6-59
Shot or Treated.
Contractor. Helmerich & Payne
Issued. 10-31-59

County Finney
KANSAS



CASING:

8 5/8" 785' cem w/500 sx.
5 1/2" 5189' cem w/650 sx.

Elevation. 2982' DF

Production. 138 BOPD

Figures indicate Bottom of Formations.

sand	270
sand & shale	609
sand & red bed	910
red bed	1835
red bed, sand & shale	1985
sand & shale	2485
shale & lime	2525
lime & shale	2780
lime	3545
lime & shale	4002
lime	4911
lime & shale	5027
lime	5190
Total Depth	

TOPS: ELECTRIC

Topeka	3453
Heebner	3876
Toronto	3893
Lansing	3922
Base Kansas City	4481
Marmaton	4500
Cherokee	4652
Atoka	4861
Morrow Shale	4921
Morrow Sand	4969-4977
St. Gen.	4990
St. Louis	5054
"B" Zone	5056-5062
"C" Zone	5130-5137
"D" Zone	5165-5171