

33-26-34W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY
Farm - Jonos No. 3

SEC. 33 T. 26 R. 34W
NEc SW

Total Depth. 2726'
Comm. 5-13-47 Comp. 6-23-47
Shot or Treated.
Contractor.
Issued. 12-13-47

County. Finney
KANSAS



Rotary tools - 1 to 2565
Cable tools 2565 to 2726

CASING:

10-3/4" 726' Cem. w/450 sx
7" 2560' Cem. w/750 sx

Elevation. 2972' act + sh

Production. Open Flow 11,150 MCF
Gas - 72 hr. Test.

Figures indicate Bottom of Formations.

○ sand & gravel	0-465
○ sand & clay blue	696
red bed	880
shale ^{cc} sholls	915
○ redbed & shale sholls	1225
shale, sholls & salt	1400
red bed	1600
red bed & sholls	1880
red bed, anhydrite & shells	2155
conglomerate & shells	2220
shale & sand	2245
red bed, shale sholls & anhydrite	2403
anhydrite & shale	2490
anhydrite & lime RTD	2565
limo	2592
○ shale blue	2597
limo	2632
shale blue	2647
limo	2674
limo	2726
○ Total Depth	
Tops:	
Horington	2557
Kridor	2570
Winfield	2605
Towanda	2674
○ Ft. Riley	2710