

33-26-3420


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE, INC.
Farm- Jones "O" No. 37

SEC. 33 T. 26 R. 34W
C NE SW

Total Depth. 5182'
Comm. 8-5-61 Comp. 8-19-61
Shot or Treated.
Contractor,
Issued. 11-25-61

County Finney
KANSAS



Elevation. 2976' RB

Production. 190 BOPD

CASING:

8 5/8" 775' cem w/350 sx.
4 1/2" 5177' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface	70
sand	850
red bed	2084
shale	2355
shale & Anhydrite	2893
lime & shale	3015
shale	3083
shale & lime	3569
shale & chalk	3710
lime & shale	3875
shale & chalk	4015
lime & shale	4235
shale & lime	4410
lime & shale	4455
lime	4847
lime & shale	4907
lime	5182
Total Depth	

TOPS: SCOUT

Topeka	3460
Heebner	3892
Toronto	3905
Lansing	3934
Base Kansas City	4497
Marmaton	4516
Cherokee	4662
Atoka	4869
Morrow Shale	4929
Morrow Lime	4948
St. Genevieve	4994
St. Louis	5046