

33-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE  
Farm- Jones "O" No. 38

SEC. 33 T. 26 R. 34W  
C SW SE

Total Depth. 5218'  
Comm. 9-8-61 Comp. 9-24-61  
Shot or Treated.  
Contractor.  
Cased. 1-6-62

County Finney  
KANSAS



CASING:  
8 5/8" 782' cem w/450 sx.  
5 1/2" 5214' cem w/350 sx.

Elevation. 3000 RB

Production. 149 BOPD

Figures Indicate Bottom of Formations.

surface sand	286
sand & clay	783
red bed	1116
red bed, shale & sand	1909
shale, sand & Anhydrite	2397
shale & Anhydrite	2636
lime	2764
lime & shale	4856
lime	4940
lime & shale	4980
lime	5121
sand	5186
lime	5218
Total Depth	

TOPS: SCOUT	
Topeka	3501
Heebner	3939
Toronto	3952
Lansing	3982
Base Kansas City	4548
Marmaton	4571
Cherokee	4712
Atoka	4920
Morrow	4978
St. Genevieve	5042
St. Louis	5086