

33-26-3410 ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE, INC.
Farm- Jones "O" No. 39

SEC. 33 T. 26 R. 34W
C SW SW

Total Depth. 5204'
Comm. 12-19-61 Comp. 1-5-62
Shot or Treated.
Contractor. Graham-Michaelis Drilling Co.
Issued. 1-12-63

County Finney
KANSAS



CASING:
8 5/8" 741' cem w/450 sx.
5" 5202'

Elevation. 2984' RB

Production. 112 BOPD & 9 BW

Figures Indicate Bottom of Formations.

soil & sand	330
clay & sand	785
red bed, shells & sand	1670
red bed & shells	2030
red bed & shale	2260
shale & lime	3025
lime	3116
lime & shale	3787
shale	3816
lime & shale	4225
lime	4300
lime & shale	4505
lime	4893
lime & shale	4984
lime	5204 RTD
Total Depth	

TOPS: LANE WELLS LOG

Topeka	3472
Heebner	3900
Toronto	3920
Lansing	3944
Base Kansas City	4506
Marmaton	4528
Cherokee	4673
Atoka	4875
Morrow	4957
Ste. Genevieve	5005
St. Louis	5071

JONES "0" #39

State Geological Survey
WICHITA FRANCIS
33-26-34W

RECORD:

LOCATION:

SW/4 SW/4 Section 33-26S-34W
Finney County, Kansas

Commenced: 12/19/61
Completed: 1/5/62
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Co.
Liberal Division
P. O. Box 896
Liberal, Kansas

CASING RECORD:

36 Jts. 8-5/8" Casing
Cemented w/350 sx Pozmix 2% cc
followed w/100 sx HA-5

	LOC
Sand & Sand	0 - 330
Clay & Sand	330 - 785
Red Bed, Shells & Sand	785 - 1670
Red Bed & Shells	1670 - 2030
Red Bed & Shale	2030 - 2260
Shale & Lime	2260 - 3025
Lime	3025 - 3116
Lime & Shale	3116 - 3787
Shale	3787 - 3816
Lime & Shale	3816 - 4225
Lime	4225 - 4300
Lime & Shale	4300 - 4505
Lime	4505 - 4893
Lime & Shale	4893 - 4984
Lime	4984 - 5204

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1962

CONSERVATION DIVISION
Wichita, Kansas

5204' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY
LIBERAL DIVISION

By H. R. Michaelis
H. R. Michaelis