

33-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HELMERICH & PAYNE, INC.
Farm- U.S.A. "A" No. 14

SEC. 33 T. 26 R. 34W
C SW NW

Total Depth. 5200'
Comm. 4-15-60 Comp. 4-27-60
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 7-30-60

County Finney
KANSAS



Elevation. 2973' DF

Production. 74 BOPD

CASING:

8 5/8" 806' w/325 sx cem.
5 1/2" 5200'

Figures Indicate Bottom of Formations.

surface sand	139
shale	700
sand, red bed	815
red bed	2273
shale, sand	2517
anhydrite, shale	2590
anhydrite, lime, shale	2772
lime, shale	3674
lime	3925
lime, shale	4145
lime	4290
lime, shale	4530
lime	4576
lime, shale	5078
lime	5146
lime, shale	5200
Total Depth	

TOPS:

Topeka	3455
Heebner	3887
Toronto	3903
Lansing	3933
B/Kansas City	4495
Marmaton	4517
Cherokee	4661
Atoka	4871
Morrow	4931
St. Genevieve	4999
St. Louis	5056
"B" Zone	5057-5081
Stray Zone	5103-5112
"C" Zone	5134-5140
"D" "	5169-5176