

4-26-35W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - MAGNOLIA PETRO. CO.
Farm - Wm. T. Gildart No. 1

SEC. 4 T. 26 R. 35W
SW SW NE

Total Depth. 2775' K.B.
Comm. 6-6-49 Comp. 6-15-49
Shot or Treated. Acidized
Contractor. Barnett Drilg. Co.
Issued. 8-13-49

County. Kearny

KANSAS



Elevation. 3001 *and*

Production. 31,080,000 gas

CASING:

10-3/4" OD 845' Cem. W/500 Sx.
6-5/8" OD 2774' Cem. W/1000 Sx.

Figures Indicate Bottom of Formations.

sand	95
gravel	210
clay & sand	320
sand	330
shale & shells	765
sand	785
red bed	850
red bed & shells	1400
sand	1680
shale & shells	2040
red bed & shells	2240
shale & shells	2370
lime brkn & gypsum	2430
lime	2550
lime & shale	2660
lime	2710
lime & shale	2775 K.B.
Total Depth	

Top Towanda 2636 K.B.

Ran Halliburton electric log

Perf. 2677-2704 W/144 sh.,
acid. W/7000 gals.
Perf. 2634-58 W/96 sh.,
acid. W/7000 gals.
Perf. 2571-98 W/120 sh.,
acid. W/7000 gals.
Perf. 2540-54 W/72 sh.,
acid. W/7000 gals.
Perf. 2514-32 W/96 sh.,
acid. W/7000 gals.
Perf. 2486-95 W/48 sh.,
acid. W/7000 gals.