

10-26-35W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY
Farm - Citizens Bldg. & No. 9
Loan

SEC. 10 T. 26 R. 35W
N. N. SE

Total Depth. 3741'

Comm. 10-2-47

Comp. 11-4-47


Shot or Treated.

Contractor.

Issued. 2-21-48

County. Kearny

KANSAS



Elevation. _____

Production. 1,048,000 gas.

CASING:
10 3/4" 806' cem. 350 sx.
7" 2538' cem. 750 sx.
5-1/2" liner 2513'

Figures indicate Bottom of Formations.

surface sand	125
surface sand & shale	260
sand & clay	315
sand & shale	765
red bed	816
shale & red bed	1035
red bed & shale	1310
red bed & shale	1620
shale	1880
lime & shale	2430
shale & lime shells	2510
lime	2639
broken lime & shale	2659
lime	2741
Total Depth.	

TOPS:
Herrington 2546
Krider 2571
Winfield 2606
Upper Fort Riley 2672
Lower Fort Riley 2714

Open Flow 7,495 MCF 72 hrs.
Deliverability 10,000 & 3,000
15% 4,000 - 7 1/2%.