

11-26-35W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company WHITE EAGLE OIL COMPANY
Farm Citizens Bldg. & No. 10
Loc n


SEC. 11 T. 26 R35W
N^W NW SE
2310' NS1 & 330' EW1 SE¹/₂

Total Depth. 2740'
Comm. 9-15-47
Shot or Treated.
Contractor.
Issued. 2-21-48

Comp. 10-21-47

County. Kearny

KANSAS



Elevation. _____

Production. 945,000 gas.

CASING:

13 3/4" 720 cem. 350 sx.
7" 2533 cem. 750 sx.
5 1/2" liner 2502'

Figures Indicate Bottom of Formations.

surface sand & shale	315
shale & sand	760
red bed	817
red bed & sand	1415
shale	1760
shale & lime	1980
shale	2185
shale & lime	2330
lime	2535
lime & shale	2559
lime	2588
broken lime & shale	2598
lime	2690
broken lime & shale	2703
lime	2740
Total Depth.	

TOPS:

Herrington	2548
Krider	2571
Winfield	2606
Upper Fort Riley	2670
Lower Fort Riley	2714

Open Flow 7,495 MCF on 72 hour test
Deliversability:
3,000 gals.
10,000 "
4,000 gals. 7 1/2%