

13-26-356


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PANHANDLE DEVELOPMENT CO., INC.  
Farm- White No. 1

SEC. 13 T. 26 R. 35W  
C NE NE

Total Depth. 5185'  
Comm. Comp.  
Shot or Treated.  
Contractor.  
Issued. 8-17-63

County Kearny  
KANSAS



CASING:  
8 5/8" 698.86' cem w/425 sx.

Elevation. 3000' RB

Production. DRY

Figures indicate Bottom of Formations.

sand, red beds & shells	700
red beds	720
red beds & anhydrite	1080
red beds, anhydrite & sand	1440
anhydrite & red beds	2030
anhydrite & shale	2240
shale & shells	2415
lime & shale	4140
lime	4965
lime & shale	5022
lime w/thin shale stringers	5185 RTD
Total Depth	

TOPS: SCOUT	
Council Grove	2811
Topeka	3428
Heebner	3840
Toronto	3860
Lansing	3890
Base Kansas City	4444
Marmaton	4460
Cherokee	4620
Atoka	4822
Morrow	4884
Morrow Sand	4963
Ste. Genevieve	4979
St. Louis	5076
"C" Zone	5130
"D" Zone	5172