

13-26-35W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - WHITE EAGLE COMPANY
Farm White No. 3

SEC. 13 T. 26 R. 35W
SW SW NE
330' N SL 330' E WL NE $\frac{1}{4}$

Total Depth. 2695'
Comm. 7-30-47 Comp. 8-39-47
Shot or Treated. Acidized
Contractor.
Issued. 2-21-48

County. Kearny
KANSAS



CASING:
10 3/4" 800' cem. w/350 sx
7" 2483' cem. w/750 sx
5 1/2" liner 2461'

Elevation. _____

Production. 1,503,000

Figures indicate Bottom of Formations.

sand	100
surface sand	350
sand & gravel	425
shale & red bed	445
white clay	470
shale & sand	630
shale	785
red bed	1140
red bed & sand	1205
red bed	1218
salt red bed	1295
red bed & sand	1660
red bed	1830
shale & red bed	1940
shale & sand	1975
lime & shale	2030
shale	2171
shale & lime	2330
lime	2360
shale & lime	2423
lime	2487 RTD
lime	2496
shale	2500
lime	2695

Total Depth 2695

TCPS:

Herington	2506
Krader	2520
Winfield	2553
Upper Fort Riley	2612
Lower Fort Riley	2664

Open Flow 13,144 MCF Lenght of test
72 hours. (Through Casing)
Acidized 10,000 & 3,000 - 15% &
4000 gals 7 1/2%.

Rotary tools from 0-2487
Cable tools from 2487-2695