

15-26-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL CO.
Farm - Citizens Bldg. & No. 11
Loan

SEC. 15 T. 26 R. 35W
C/S 2 1/2 SW SW NE
330' NS1 & 330' EWL NE 1/4.

Total Depth. 2720'
Comm. 1-25-48 Comp. 2-19-48
Shot or Treated. Acid. W/13,000 15% & 4,000 gals. 7 1/2% acid.
Contractor.
Issued. 8-14-48 Rotary Tools 0' to 2481'
Cable Tools 2481' to 2720'

County. Kearny
KANSAS



CASING:
10-3/4" 793' Cem. W/400 Sx.
7" 2477' Cem. W/750 Sx.

Elevation. 3003.2nd.

Production. 2,273,000 Gas

Figures Indicate Bottom of Formations.

sand & clay	0-340
clay & shells	765
shale gy	800
red bed	900
red bed sdy.	1280
red bed & shells	1400
salt & red bed	1575
red bed & shells	1860
anhy. & red bed	1975
lime & shale red	2055
red bed & shells	2155
anhy. & blue shale	2280
shale blue	2360
lime	2352
anhydrite Brkn	2425
anhy. & shale	2517
shale	2520
lime	2605
shale red	2626
lime	2628
brkn shale & lime	2636
lime	2668
lime brkn	2679
lime ded	2720
Total Depth	

Tops:
Herrington 2521-2538
Kramer 2540-2559
Winfield 2576-2605
Upper Ft. Riley 2632-2664
Lower Ft. Riley 2683-2720