


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - HELMERICH AND PAYNE, INCORPORATED  
Farm - Citizens Building and Loan No. 8

SEC. 22 T. 26 R. 35W  
SWc NE

Total Depth. 2699'  
Comm. 8-12-47 Comp. 9-12-47  
Shot or Treated.  
Contractor.  
Issued. 12-13-47

County. Kearny  
KANSAS



Elevation. \_\_\_\_\_

Production. 14,740 MCF Gas  
72 hour test.

CASING:

10-3/4" 780' Com. w/400 sx  
7" 2490' Com. w/750 sx

Figures Indicate Bottom of Formations.

sand & shells	0-400
clay	485
sand	535
shale blue	645
limo & shale	750
rod bed	1770
shale & anhydrite	1830
anhydrite	1290
anhydrite & shale	1960
shale	2030
limo & shale	2260
lime cherty	2350
limo	2425
limo & shale	2500
limo	2618
conglomerate & limo	2625
limo	2699
Total Depth	

TOPS:

Herrington	2489
Krider	2509
Winfield	2543
Upper Ft. Riley	2595
Lower Ft. Riley	2647

Gas - 14,740 MCF 72 Hr. Test