

23-26-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY
Farm - Citizens Building and Loan No. 3

SEC. 23 T. 26 R. 35W
SW $\frac{1}{4}$ NE
330' NS1 & 330' EW1 NE $\frac{1}{4}$

County. Kearny
KANSAS

Total Depth. 2674'

Comm. 6-1-47

Comp. 6-10-47

Shot or Treated. Acidized

Contractor.

Issued. 12-13-47

Rotary tools 1' to 2500'

Cable tools 2500' to 2674'

CASING:

10-3/4" 650' Com. w/450 sx
7" 2487' Com. w/750 sx

Elevation. 2992' sch. sh

Production. 24 hour Open Flow
17,340 MCF Gas

Figures indicate Bottom of Formations.

sand, gravel & clay	0-195
clay sdy	440
sand & clay blue	445
red rock & clay red	455
sand & gravel	600
shale blue	709
shale gy	720
red bed	750
red bed & shale	890
red bed, shale & shells	1735
red bed, anhydrite & shells	1855
sand & shale	2145
shale & anhydrite	2449
limo & shale RTD	2500
limo	2504
shale brkn	2507
limo, first gas at 2508'	2541
shale brwn & limo brkn	2560
limo	2591
shale brwn	2611
limo	2654
shale blue	2658
shale red	2666
limo	2674
Total Depth	

Tops:

Herington	2505-2522
Krider	2528-2544
Winfield	2570-2588
Upper Ft. Riley	2622-2650
Lower Ft. Riley	2666

Acid. w/12,000 gals., 15% acid
" w/ 6,000 gals., 7 $\frac{1}{2}$ % acid