

26-26-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY
Farm - Pottor No. 1

SEC. 26 T. 26 R. 35W
SEc NW
330' NS1 & 2310' EW1 NW $\frac{1}{4}$

Total Depth. 2800'
Comm. 9-26-47 Comp. 9-29-47
Shot or Treated. Acidized
Contractor.
Issued. 12-13-47

County. Kearny

KANSAS



Rotary Tools: 0-2620
Cable Tools: 2620-2800

Elevation. 3001^{ft}

Production. Open Flow 12,914
MCF Gas - 72 hr. test

CASING:

10-3/4" 761' Com. w/400 sx
7" 2596' Com. w/750 sx

Figures Indicate Bottom of Formations.

sand	0-150
sand & shale	525
sand	600
shale & shells	739
red bed	1320
red bed & anhydrite	1380
red bed	1995
shale & lime	2325
anhydrite	2392
shale & anhydrite	2428
lime	2460
lime cherty	2528
shale & anhydrite	2563
lime	2750
shale red	2756
lime	2800
Total Depth	

Tops:

Horington	2596-2610
Krider	2613-2632
Winfield	2648-2675
Upper Ft. Riley	2703-2740
Lower Ft. Riley	2754-2783

Acid. w/15,000 gals., 15% acid.