

27-26-35W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HELMERICH AND PAYNE, INCORPORATED
Farm - Citizens Building & Loan No. 5

SEC. 27 T. 26 R. 35W
NW 1/4 SE

Total Depth. 2770'

Comm. 7-31-47


Comp. 8-27-47

Shot or Treated.

Contractor.

Issued. 12-13-47

County. Kearny
KANSAS



Elevation. 3001 act

Production. 10,233 MCF Gas in
72 hour test.

CASING:

10-3/4" 780' Com. w/400 sx
7" 2521' Com. w/750 sx
5-1/2" 2770'

Figures Indicate Bottom of Formations.

sand & shells	0-400
shale & shells	450
red bed	470
shale	750
red bed	1640
red bed & shale	1900
anhydrite	2010
shale & red bed	2135
limo & shale	2365
lime	2452
lime & shale	2540
shale	2542
limo & shale	2547
lime	2636
lime mod.	2641
lime hrd	2651
lime mod.	2770
Total Depth	

TOPS:

Herzington	2577
Krider	2598
Winfield	2632
Upper Ft. Riley	2687
Lower Ft. Riley	2738