

25-26-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL COMPANY  
Farm - Citizens Building and Loan No. 4


SEC. 25 T. 26 R. 35W  
SEc NW  
330' NS1 & 2310' EW1 NW $\frac{1}{4}$

Total Depth. 2732'  
Comm. 7-9-47  
Shot or Treated. Acidized  
Contractor.  
Issued. 12-13-47

Comp. 7-16-47

Rotary tools 1' to 2520'  
Cable tools 2520' to 2732'

County. Kearny  
KANSAS



Elevation. 3001 set

CASING:  
10-3/4" 760' Com. w/350 sx  
7" 2505' Com. w/800 sx

Production. 20 min. Open Flow  
20,332 MCF Gas

Figures Indicate Bottom of Formations.

|                           |       |
|---------------------------|-------|
| sand & clay sdy           | 0-425 |
| red rock                  | 435   |
| sand & clay blue          | 730   |
| red bed                   | 1317  |
| red bed & sand            | 1810  |
| shale & shells            | 1990  |
| shale, shells & anhydrite | 2145  |
| shale & anhydrite         | 2380  |
| shale & limo              | 2462  |
| anhydrite & limo          | 2520  |
| shale blue & red RTD      | 2529  |
| limo                      | 2572  |
| shale blue                | 2577  |
| shale brwn                | 2588  |
| limo & shale              | 2618  |
| shale red & blue          | 2642  |
| limo                      | 2680  |
| shale blue                | 2692  |
| limo                      | 2732  |
| Total Depth               |       |

Tops:  
Horington 2532-2551  
Kridor 2555-2574  
Winfield 2600-2613  
Ft. Riley 2644-2680

Acidized w/13,000 gals., 15% acid.  
" w/ 4,000 gals., 7 $\frac{1}{2}$ % acid.