

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

28-26-35W

Company - MAGNOLIA PETROLEUM COMPANY
Farm - Wampler-U.S.A. Unit No. 1

SEC. 28 T. 26S R. 35W
NW NW SE

Total Depth. 2845' K.B.

Comm. 9-22-48

Comp. 10-2-48


Shot or Treated. Acidized

Contractor Corbett-Barbour Drlg. Co.

Issued. 12-25-48

County. Kearny

KANSAS



Elevation. 3081' Ind.

Production. 22,000 MCF gas

CASING:

10 3/4" 833' cem. w/450 sx.
7" 2844' cem. w/1000 sx.

Figures indicate Bottom of Formations.

sand & clay	125
sand & shale	275
sand & shells	515
sand & clay	525
red bed	550
sand & blue shale	635
shale	675
sandy lime	795
red bed	835
red bed & shale	940
red bed	1100
anhydrite	1175
red rock	1325
shale & red rock	1595
sand & shale	1945
red rock & anhydrite	2000
shale & red rock	2065
shale & shells	2210
shale & anhydrite	2390
lime	2450
lime & gypsum	2490
anhydrite & lime	2540
chalky lime	2595
lime	2635
anhydrite & lime	2665
lime	2845

Total Depth 2845 K.B.

Top Towanda 2732 K.B.

Ran Halliburton electric log

perf. 2774-2801 w/144 sh., 7000 A.
perf. 2734-52 w/96 sh., 7000 A.
perf. 2671-94 w/96 sh., 7000A
perf. 2640-54 w/72 sh., 7000 A.
perf. 2610-33 w/120 sh., 7000A.