

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 093 — 20725
County NumberState Geological Survey
WICHITA, BRANCH

S. 28 T. 26S R. 35 W

Loc. SW SW NE

Operator

Mobil Oil Corporation

Address

P.O. Box 5444 Denver, CO 80217

Well No.

2

Lease Name

Wampler - USA Unit

Footage Location

2320 feet from (N) $\frac{1}{2}$ line

2480

feet from (E) $\frac{1}{2}$ line

Principal Contractor

Wakefield Drilling Co.

Geologist

V. C. Andresen

Spud Date

3/11/81

Date Completed

4-10-81

Total Depth

3085

P.B.T.D.


Directional Deviation

3/4° @ 2003'

Oil and/or Gas Purchaser

CITIES SERVICE CO.

County Kearny

640 Acres
N

Locate well correctly

Elev.: Gr. 3064'

DF KB 3072'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface casing	12 $\frac{1}{4}$ "	8-5/8"	24#	843'	Class H	150	12% gel + 3% CaCl ₂
					Class H	150	3% CaCl ₂
production casing	7-7/8"	5 $\frac{1}{2}$ "	14#	3085	HOWCO LITE	500	
					Class H Neat	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			SEE ATTACHED		
Size	Setting depth	Packer set at			
2-3/8"	3030'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
6000 gals acid with 100 balls	2891-3017
90,000 gals gelled water and 210,000# 20-40 sand	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
awaiting connections		pumping			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	N/A 5/12/81 MCF		bbls. CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s)	
awaiting connections				2891-3017	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

erator

Mobil Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
gas

Well No.

2

Lease Name

Wampler - USA

S 28 T 26S R 35 ~~XX~~
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	46	Stone Corral	1842
Sand, Clay & Blue Shale	46	763		
Red Bed	763	905	Chase	2582
Red Bed & Gyp	905	1460		
Sand	1460	1565	Council Grove	2882
Shale & Gyp	1565	1695		
Shale & Anhydrite	1695	1965		
Shale	1965	2345		
Shale & Lime	2345	2810		
Lime & Shale	2810	3080		
Lime	3080	3085		
R.T.D.		3085		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

C. J. PARK

Signature

PRODUCING ACCOUNTING SUPERVISOR

Title

5-13-81

Date

PJ

28-26-35w

WAMPLER-USA UNIT #2

KEARNY COUNTY, KANSAS

PERFORATION RECORD

A ZONE	2891-2894	
	2904-2908	
	2912-2916	
	2920-2928	2 SPF
	2930-2932	
	2942-2945	
	2930-2932	
	2942-2945	

B 3 Zone	2994-2999	2 SPF
----------	-----------	-------

B 4 Zone	3011-3017	2 SPF
----------	-----------	-------
