

31-26-35W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. MAGNOLIA PETROLEUM CO.
Farm. E. S. Boase Unit No. 1

SEC. 31 T. 26 R. 35W
NW NW SE

Total Depth. 2785' K.B.
Comm. 4-9-49 Comp. 4-19-49
Shot or Treated. Acidized
Contractor. Mallonee Drlg. Co.
Issued. 6-18-49

County. Kearny
KANSAS



CASING:
10-3/4" 326' Cem. W/425 Sx.
5-1/2" 2784' Cem. W/1000 Sx.

Elevation. 3070' *Ind.*

Production. 15,900,000 gas

Figures indicate Bottom of Formations.

clay & sand	170
sand & shale	550
shale blue & lime	
sandy	675
sand	725
shale & sand	740
sand & gravel	772
red bed	1260
red bed & anhydrite	1480
red bed & shells	1740
anhydrite	1950
anhy. & sdy lime	2015
lime & shale	2085
shale & lime shells	2230
shale & shells	2305
anhydrite	2395
anhydrite & red bed	2460
anhydrite	2565
lime sdy & shale	2610
lime & shale	2730
lime	2785 K.B.
Total Depth	

Top Towanda 2665 K.B.

Ran Halliburton electric log

Perf. 2704-31 W/144 sh., acid. W/7000 gals.
Perf. 2666-84 W/96 sh., acid. W/7000 gals.
Perf. 2610-26 W/72 sh., acid. W/7000 gals.
Perf. 2548-84 W/168 sh. acid. W/7000 gals.