

34-26-35W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - HELMERICH AND PAYNE, INC.
Farm - Citizens Building and Loan No. 6

SEC. 34 T. 26 R. 35W
SEc NW

Total Depth. 2753'

Comm. 7-19-47

Comp. 7-30-47

Shot or Treated.

Contractor.

Issued. 12-13-47

County. Kearny

KANSAS



Elevation. _____

Production. 20 min Open Flow
14,800 MCF Ga.

CASING:

10-3/4" 790' Cem. w/400 sx
7" 2550' Cem. w/700 sx

Figures Indicate Bottom of Formations.

sand, gravel & clay	0-415
clay & sand	585
shale blue	785
shale & sand	808
red bed	850
shale blue & shells	
sticky	900
red bed, some shale &	
shells	1600
shale, shells & sand	1725
shale & shells	1930
anhydrite	1950
shale & limo strks	2055
lime & shale	2105
limo	2315
limo & anhydrite	2360
limo	2466
limo & shale	2509
limo	2556
limo mod.	2591
limo	2601
shale	2604
limo	2608
shale	2610
limo & shale	2615
limo	2635
limo hrd	2645
limo	2671
limo mod.	2683
limo hrd	2696
limo brkn	2705
limo & shale	2715
limo	2723
limo mod.	2741
limo	2753
Total Depth	

Tops:

Herington	2558
Kridor	2616
Winfield	2670
Lower Ft. Riley	2714