


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- KANSAS-NEBRASKA NATURAL GAS CO.  
Farm- Lee No. 22

SEC. 6 T. 26 R. 36W  
SW SW NE

Total Depth. 2665  
Comm. 3-31-53 Comp. 4-9-53  
Shot or Treated.  
Contractor. Honaker Drilling Co.  
Issued. 8-8-53

County Kearny  
KANSAS



CASING:  
10 3/4 set at 557' w/ 350 sx cement  
7 5/8 set at 2654' w/ 1000 sx cement

Elevation. 3051

Production. 3,272,000 gas

Figures indicate Bottom of Formations.

top soil & sand	67
sand	273
sand & gravel	460
clay & sand	484
sand & shale	625
shale, sand & red bed	1000
red bed	1290
gyp & shale	1355
red rock & shale	1480
red bed	1725
anhydrite	1755
lime & shale	2090
red bed & shale	2281
lime & shale	2600
lime	2665
Total Depth	

SCOUT TOPS:	
Herrington	2424
Krider	2444
Winfield	2486
Upper Ft. Riley	2538
Lower Ft. Riley	2588