

WELL LOG

COMPANY Kansas Nebraska Natural Gas Company, Inc.

SEC. 5-26S-36W

FARM Lee

NO. 25-4

LOC. 2410' FNL & 560' FEL


TOTAL DEPTH 5100'

COUNTY Kearny

COMM. 7-15-76

COMP. 7-25-76

CONTRACTOR Zenith Drilling Corporation, Inc.



CASING

844' of 8 5/8" casing with 550 sacks cement
3019' of 4 1/2" casing, with 900 sacks cement

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

845	Sand
1470	Sand & Red Bed
1808	Sand
1818	Anhydrite
2085	Shale & Shells
2260	Shale
2660	Lime & Shale
2935	Shale & Shells
4912	Lime & Shale
5010	Shale & Sandy Lime
5087	Lime & Shale
5100	Lime