


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- KANSAS-NEBRASKA NATURAL GAS CO., INC.  
Farm- Lee No. 16

SEC. 7 T. 26 R. 36W  
NE NE NE SW  
75' S, 100' W of  
center  
County Kearny  
KANSAS

Total Depth. 2695  
Comm. 5-31-51 Comp. 6-7-51  
Shot or Treated.  
Contractor.  
Issued. 10-13-51



CASING:  
10 3/4" 560' cem. w/350 sx circ.  
7" 2652' cem. w/900 sx circ.

Elevation. 3045

Production. 2,978,000 gas

Figures Indicate Bottom of Formations.

sand, gravel & gyp	460
sand & gravel	500
clay blue	660
clay & sand stone	750
red bed & gyp	990
gyp, red, bed & sand	
stone	1270
red bed & sand	1640
red bed, gyp & anhy.	
streaks	1840
shale & anhy.	1970
shale & lime	2295
shale, lime & anhy	2350
lime & shale	2665
shale, lime & anhy.	2695
Total Depth	

Scout Tops:	
Herington-Krider	2418
Winfield	2480
Upper Ft. Riley	2532
Lower Ft. Riley	2580