

18-26-36W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HELMERICH & PAYNE, INC.
Farm - Hilliard No. 3.

SEC. ¹⁸20 T. 26 R. 36 W
SE NE SW

Total Depth. 2625'
Comm. 8-29-47 Comp. 9-23-47
Shot or Treated.
Contractor.
Issued. 12-20-47

County. Kearny
KANSAS



CASING:
10 3/4" 792' Cem.
7" 2428' Cem.
5 1/2" liner 225' 3" at 2625'

Elevation. _____

Production. 7,234,000 G.

Figures Indicate Bottom of Formations.

surface clay	0-324
sand, gravel, shale	460
sand, gravel	580
shale gy & shells	780
red bed	1290
red bed & anhydrite	1400
red bed, shell, sand	1545
red bed & sand	1695
shak red	1775
shale red & sand	1840
anhydrite & shale	1885
shale red & sand	1930
red bed, anhydrite & shell	2039
shale & shells	2235
lime	2320
anhydrite & red shale	2335
lime & shale	2402
lime	2465
lime hd	2470
lime	2472
shale red & blue	2484
lime	2511
shale red	2522
shale	2537
lime	2625
Total Depth.	

Tops: Herington 2421
Kridner 2442
Winfield 2478
Upper Ft. Riley 2534
Lower Ft. Riley 2584

Gas 7,234 MCF 72-hr test