

20.26-36W

SEC. 20 T. 26 R. 36W

T. 26

36W

County. Kearney

KANSAS

Comm. 9-27-47

Comp. 10-5-47

Shot or Treated. Acidized

Contractor.

issued 2-21-48

CASING:

10 3/4" 765' cem. w/400 sx

7" 2519' cem. w/500 sx

5. 1 1/2" liner. 2167 1/4" .

Elevation. _____

Production. 1,593,000 Gas

Figures Indicate Bottom of Formations.

sand & gravel	795
red bed & sand	915
red bed & anhydrite	1435
red bed	1790
red bed, anhydrite	1915
red shale, & shells	2065
red bed	2200
lime & shale	2270
lime	2275
lime & shale	2345
cherty lime & shale	2370
lime & shale	2496
lime	RTD 2530
lime	2550
shale	2555
shale & lime	2570
lime	2606
shale red & lime shells	2625
lime	2720

Total Depth 2720'

TIPS:

Horington 2516

Krider 2526

Winfield 2573

Upper Ft Riley 2638

Lower Ft Riley 2679

Open flow (through casing) 11,998

MEF 72 Hour test

Acidized: 10,000 & 3,000 15% & .

1,000 gals $7\frac{1}{2}\%$.

Open Flow 1,593 MCF 72 hr Test

Deliverability Acidized 10,000

2c 3,000 - 15% & f,000 Gals $7\frac{1}{2}$ "