

25-26-36W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - MAGNOLIA PETROLEUM CO.  
Farm - C. A. Loucks Unit No. 1

SEC. 25 T. 26 R. 36W  
NW NW SE

Total Depth. 2800' K.B.  
Comm. 4-9-49 Comp. 4-18-49  
Shot or Treated. Acidized  
Contractor. Barnett Lrlg. Co.  
Issued. 6-18-49

County. Kearny  
KANSAS



Elevation. 3100 *ft*

Production. 9,240,000 gas

Figures Indicate Bottom of Formations.

surface soil & sand	40
clay sdy	95
sand	210
sand, shale & shells	315
shale & shells	710
sand	750
shale & shells	790
red bed & shells	900
red bed	1305
shale & shells	1465
red bed, shale & shells	1720
shale & shells	1890
salt	1925
shale & shells	1965
red bed, shale & shells	2040
shale	2130
shale & lime	2590
lime	2795
lime & shale	2800 KB
Total Depth	

Top Towanda 2695 KB

Ran Halliburton Electric log

Perf. 2733-62	W/1 1/4 sh. acid.	W/7000 gals.
" 2696-2716	W/96 sh Acid	W/7000 gals.
" 2638-58	W/96 shl, acid.	W/7000 gals.
" 2598-2616	W/96 sh. acid	W/7000 gals.
" 2576-94	W/96 sh., acid.	W/7000 gals.