

26-26-36W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - MAGNOLIA PETROLEUM COMPANY  
Farm - Hugoton USA "B" No. 1

SEC. 26 T. 26 R. 36W  
CW<sup>1</sup>/<sub>2</sub> W<sup>1</sup>/<sub>2</sub> NW

Total Depth. 2768 KB  
Comm. 4-20-49 Comp. 4-29-49  
Shot or Treated. Acid.  
Contractor. Barnett Drilling Co.  
Issued. 6-11-49

County. Kearny  
KANSAS



Elevation. 3079 *ft*

Production. 15,100,000 gas

CASING:  
10 3/4" 811' cem w/500 sx.  
6 5/8" 2767' cem w/1000 sx.

Figures Indicate Bottom of Formations.

|                    |         |
|--------------------|---------|
| surface soil, sand | 20      |
| sand               | 215     |
| sand, clay, shells | 450     |
| shale, shells      | 630     |
| shale              | 780     |
| red bed, shells    | 812     |
| shale red, shells  | 1440    |
| sand               | 1680    |
| shale              | 1800    |
| shale, shells      | 2370    |
| shale, lime        | 2555    |
| lime               | 2600    |
| lime, shale        | 2710    |
| lime               | 2745    |
| lime, shale        | 2768 KB |
| Total Depth        |         |

Tops:  
Towanda 2658 KB

Ran Halliburton Elec. log.

Perf. 2700-28 w/144 sh., acid w/7000 gals.  
Perf. 2656-80 w/120 sh., acid w/7000 gals.  
Perf. 2593-2620 w/120 sh., acid w/7000 gals.  
Perf. 2538-78 w/192 sh., acid w/15000 gals.  
Perf. 2513-22 w/48 sh., acid w/7000 gals.