

MID CONTINENT PETROLEUM CORPORATION
WELL RECORD C.A. WOOD NO.1

NE 1/4 Sec. 4-20S-10W, Rice County, Kansas
330' from North line & 330' from East line
Commenced August 5, 1936; Completed October 20, 1936; Prod 2432 bbls.
Contractor; Mac & Stauffer

FORMATION RECORD

sand	0	110
rock	110	120
shale	120	168
shale	168	190
sand rock	190	225
shale	225	250
shale	250	397
shale & shells	397	597
shale	597	650
lime	650	835
shale	835	900
lime	900	950
salt	950	1225
lime broken	1225	1300
lime	1300	1435
shale	1435	1550
lime	1550	1585
shale & shells	1585	1695
shale sandy	1695	1788
lime	1788	1895
shale	1895	1920
lime	1920	1935
shale	1935	2300
shale & lime blue	2300	2340
lime gray	2340	2470
lime white	2470	2600
lime hard white	2600	2615
lime gray	2615	2990
shale	2990	3025
lime	3025	3079

NOTE: Dropped sledge hammer in hole, twisted off pipe & plugged back to 2350

Set Hasman whipstock at 2350

lime	2350	2520
lime broken	2520	2562
lime gray	2562	2594
lime	2594	3020
lime & shale	3020	3035
Lime K.G.	3035	3285
shale brown	3285	3293
shale green	3293	3300
conglomerate	3300	3307
SILICIOUS LIME	3307	3315 good show oil
do do	3315	3317 " " " T.D.

CASING RECORD

SIZE	CASING SPOT	CEMENT
13"OD40#	189'	200 sacks
7"OD24#	3307	250 "