

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

10-26-37W


Company - WHITE EAGLE OIL COMPANY
Farm Hillyard No. 2

SEC. 10 T. 26 R. 37W
SE SE NW
330' N of SL 2310' E of WL
NW $\frac{1}{4}$

Total Depth. 2625'
Comm. 8-16-47
Shot or Treated. Acidized
Contractor.
Issued. 2-21-48

Comp. 9-10-47

County. Kearny
KANSAS



Elevation. 3054 *sea*

Production. 923,000 Gas

CASING:
10 3/4" 595' cem w/400 sx.
7" 2355' cem w/750 sx.
5 1/2" liner 2530'

Figures Indicate Bottom of Formations.

surface clay	615
red bed	800
red bed, & anhydrite	1300
red bed, shells & sand	1465
sand & red bed	1640
red bed	1715
red bed & shell	1780
anhydrite & red bed	1890
red bed & shells	2105
red bed, anhydrite	2170
shale	2225
anhydrite & shale	2319
lime & shale	2365
lime	2387
shale & lime, shells	2400
broken lime & shale	2410
lime & shale	2428
lime	2440
shale & shells	2460
shale & lime	2500
broken lime	2524
lime	2580
shale, blue	2585
shale	2604
lime	2625

Total Depth 2625'

TOPS:
Herington 2351
Hrider 2370
Winfield 2410
Upper Fort Riley 2464
Lower Fort Riley 2516
Florence 2604

Open flow (through casing) 6,498 MCF
72 hour test.
Acidized: 13,000 15%
4,000 7 1/2%

Rotary tools from 0-2365
Cable tools from 2365-2625