

MID CONTINENT PETROLEUM CORPORATION
WELL RECORD C.A. WOOD NO. 3

NE $\frac{1}{4}$ Sec. 4-20S-10W Rice County, Kansas
990' from North line & 330' from East line
Commenced October 12, 1936; Completed November 17, 1936; Prod. 1179 Bbls.
Contractor; Mac & Stauffer Drilling Co.

FORMATION RECORD

surface	0	25
sand water	25	150
shale	150	170
shale	170	188
red bed	188	335
shale	335	415
shale & shells	415	780
shale	780	820
lime white	820	975
salt	975	1080
shale & shells	1080	1270
lime broken	1270	1300
lime	1300	1715
shale	1715	1770
lime	1770	1870
shale	1870	1910
lime	1910	1993
shale	1993	2110
lime	2110	2215
shale	2215	2360
lime	2360	2950
shale	2950	3047
Lime K.C.	3047	3305
shale red	3305	3319
conglomerate	3319	3333
Lime Silicious	3333	3336 light show oil
" "	3336	3341 light show oil
" "	3341	3346 Good sgow oil in last foot.

CASING RECORD

SIZE	CASING SPOT	CEMENT
13" OD 50#	198'	200 sacks
7" OD 24#	3336'	250 "