

Start Sept

MID-CONTINENT PETROLEUM CORPORATION

WELL RECORD

C. A. Wood well No. 5

DESCRIPTION: NE Section 4-20-10W, Rice County, Kansas

LOCATION: 330feet from North & 1050 feet from East lines

CONTRACTOR: Mac & Stauffer

COMMENCED: 3-15-37 COMPLETED: 4-9-37

FORMATION RECORD

Shale & sand	0'	to	180'
Shale & sand	180		250
Sand & gravel	250		265
Shale	265		290
Lime & shells	290		295
Broken lime	295		395
Red bed & shale	395		495
Shale & shells	495		705
Shale & lime shells	705		880
Lime, broken	880		-1055
Salt	1055		1265
Shale & shells	1265		1480
Lime	1480		1600
Shale	1600		1670
Lime, Broken	1670		1765
Lime	1765		1865
Shale	1865		2040
Lime	2040		2065
Shale	2065		2350
Lime	2350		2445
Shale, lime & shells	2445		2525
Lime	2525		2939
Shale	2939		3015
Lime, KC	3015		3300
Conglomerate	3300		3313
Silicious lime	3313		3323 Good show oil
Total depth			3323

CASING RECORD

13"OD	40#	New LW	219'	with 250 sax
7"OD	24#	" SS	3310'	" 250 "

None pulled out

Production 2,581 bbls. (Telephone-Long)

-----