

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


14-26-37W

Company - WHITE EAGLE OIL CO.
Farm - Hillyard No. 5

SEC. 14 T. 26 R. 37W
SE SW NW
330' N of SL and
2310' E of WL of NW/4

County. Kearny
KANSAS

Total Depth. 2595'
Comm. 7-9-48 Comp. 8-9-48
Shot or Treated. Acidized
Contractor.
Issued. 10-9-48



CASING:

10 3/4" 753' Cem w/375 Sx.
7" 2388' Cem w/750 Sx.

Elevation. 3078 Ind.

Production. 30,000,000 Gas

Figures Indicate Bottom of Formations.

surface sand, clay	500
shale, blue	660
shale, sand rock	735
red rock	765
red bed	895
red rock, shale	1500
anhydrite, red bed	1585
anhydrite, shale	1735
shale, lime	1850
anhydrite, shale, and lime	1909
lime, shale	2080
lime	2170
lime, shale	2405
lime RTD	2405?
lime, medium	2420
shale	2422
lime	2430
shale, red & lime	2438
shale, lime	2443
shale, brkn & lime	2452
lime	2468
shale, lime	2508
lime, medium	2532
shale	2539
lime	2554
lime, gy & med.	2584
lime	2595
total depth	

Tops:

Herington	2392-2407
Krider	2410-2432
Winfield	2449-2476
Upper Ft. Riley	2505-2536
Lower Ft. Riley	2557-2595

Acidized w/13000 gals of 15%
and 4,000 gals of 7 1/2% acid.