

12/31/17

25.
#1 Barnhill - Cosden-Reet & Neff
Sec. 23 T 27S R7E Kansas.

Northeast Corner SW 4

Drilling Commenced Apr 5-16
" Completed Sept 5-16

0--70		Lime.	
70--125	50	Red rock.	Set 15½ casing at 110
125--265	140	Slate.	
265--269	4	Water sand.	
269--280	11	Slate.	
280--290	10	Red rock.	
290--360	70	Shelly formation.	
360--385	25	Slate.	
385--525	140	Slate & shells.	
525--540	15	Red rock.	
540--800	260	Slate & shells.	Set 12½ casing at 775.
800--830	30	Lime.	
830--940	130	Slate.	
940--995	55	Lime.	
995--1300	305	Slate & lime shells.	Set 10 casing at 1300.
1300-1310	10	Water sand.	
1310--1410	100	Slate.	
1410--1430	20	Sandy formation.	
1430--1470	40	Slate cave.	
1470--1550	80	Slate.	
1550--1605	55	Water sand.	
1605--1650	45	Slate.	
1650--1665	15	Sandy formation.	
1665--1675	10	Slate.	
1675--1680	5	Sandy formation.	
1680--1765	85	Slate & shells.	Set 8½ casing at 1722.
1765--1800	35	Lime shell.	
1800--1820	20	Slate.	
1820--1835	15	Sandy formation.	
1835--1870	35	Slate.	
1870--2000	130	Slate & lime shells.	
2000--2070	70	Slate.	
2070--2085	15	Sandy formation.	show of oil -

(continued)

Copied
11/15/17 (21)

2085--2097	12	Slate.	Set $6\frac{5}{8}$ casing at 2097.
2097--2145	48	Oil sand.	and underreamed to 2367. Showing for a 2 or 3 bbl. well.
2145--2160	15	Lime shell.	
2160--2165	5	Water sand.	
2165--2185	20	Sandy formation.	
2185--2190	5	Slate.	
2190--2200	10	Lime shell.	
2200--2215	15	Water sand.	
2215--2233	18	Slate.	
2233--2236	3	Thin shell & oil sand---	showing of oil.
2236--2277	41	Fine white water sand---	hole filled with water.
2277--2282	5	Lime shell.	
2282--2290	8	Slate.	
2290--2315	25	Water sand.	- Hole full water

(2315--)

(drilling at 2330 in slate. June 19, 1916.)

Lime shell 2370 - Set $6\frac{5}{8}$ " Casing at 2367

Small showing Oil 2647-2657 - Set $5\frac{7}{16}$ " Casing at 2777

Hole full water 2675

" " " 2817

Stopped drilling 2840 in hard lime

Hole abandoned at 2840