


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
 Farm- Anderson Gas Unit No. 1
 "B"

SEC. 10 T. 26 R. 38T
 SW SW SW NE
 150' N. of SL 150' E. of WL NE $\frac{1}{4}$

Total Depth. 2633
 Comm. 4-8-52 Comp. 4-30-52
 Shot or Treated.
 Contractor.
 Issued. 5-31-52

County Kearny
 KANSAS



CASING:

10 3/4" 585' com. w/350 sx
 7" 2608' com. w/300 sx

Elevation. 3195
 3196 (Ind)
 Production. 25,612,000 Gas

Figures Indicate Bottom of Formations.

clay & sand	125
gyp & shale	230
sand & shale	285
gyp & sand	325
shale blue	445
shale	540
red bed	725
gyp & red rock	820
red rock & sand	1040
anhydrite	1075
red rock	1165
anhydrite	1205
red rock & sand	1330
salt & red rock	1540
red rock & anhydrite	1675
anhydrite	1950
red rock	2210
shale & lime	2250
lime	2320
lime & shale	2386
lime	2495
lime & shale	2610
lime	2633
Total Depth	

Herington-Krider	3000	15%
Winfield	2000	15%
Towanda	3000	15%
All Zones	24,000	7 $\frac{1}{2}$ %

Tops:
 Herington-Krider 2437
 Winfield 2496
 Towanda 2553
 Ft. Riley 2608

Schlumberger ran Gamma-Ray
 & Micro Logs
 McCullough Tool Co. perf.
 w/6 SPF as follows:
 Herington-Krider 2437-57',
 2461-63', 2469-73', 2478-82'.
 Winfield 2496-2504', 2509-13',
 2515-18', 2522-26'.
 Towanda 2553-70', 2572-82',
 2586-89'.
 Chemical Process Co. acidized
 as follows:
 Ft. Riley 2500 15%