

KANSAS DRILLERS LOG

API No. 15 — 093 — 20,086
County Number

Operator
Amoco Production Company

Address
P. O. Box 432 - Liberal, Kansas 67901

Well No. 2 Lease Name Anderson Gas Unit "B"

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor
Service Drilling Company

Geologist

Spud Date 8-8-73 Total Depth 2867 P.B.T.D. 2865


Date Completed 9-15-73 Oil Purchaser

S. 10 T. 26 R. 38 W

Loc. 1250 FSL & 2590 FEL

County Kearny

640 Acres
N



Locate well correctly

Elev.: Gr. 3202

DF. KB 3209

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	23	665	Class "A"	385	3% CACL
Production	7-7/8	5-1/2	14	2867	Special	800	18% CACL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2	2723-30, 2739-45, 2753-58, 2772-87, 2792-2804, 2818-21
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	2773'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/ 2500 gal 15% HCL & frac w/ 100,000 gal water & 100,000# sand	2723-2821

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	10,500 MCF		bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
Waiting on pipeline connection			2723-2821		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

[illegible]