


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Eveleigh G.U. No. 1
"B"

SEC. 24 T. 26 R.38W
SW SW SW NE
150' N of SL & 150' E of WL

Total Depth. 2655
Comm. 4-24-52 Comp. 5-18-52
Shot or Treated.
Contractor.
Issued. 6-14-52

County Kearny
KANSAS



Elevation. 3197
3201 (Log)
Production. 9,797,000 gas

CASING:

8 5/8" 601' cem. w/275 sx.
5 1/2" 2633 cem. w/300 sx.

Figures Indicate Bottom of Formations.

sand, shale	225
sand, gyp, shale	335
shale blue	440
shale	550
red bed	765
anhyd., red rock	780
redrock, gyp	1040
sand	1100
anhyd., redrock	1235
salt, redrock	1510
anhyd.	1625
red rock	1810
salt	1825
salt, redrock	1860
anhyd.	1900
red rock	2200
redrock, anhyd.	2325
anhyd.	2480
anhyd., lime	2580
limo	2655
Total Depth	

Tops:

Herington-Krider	2460
Winfield	2518
Towanda	2576
Ft. Riley	2632

Ran 1 1/4" tubing set at 2638

Sch. ran Gamma Ray Micro logs:

McCullough tool Co. perf. w/6 shots per
ft. as follows:

Horington-Krider 2462-65 2467-80
2482-84 2497-2508

Winfield 2520-22, 2526-36, 2540-47,
2570-74

Towanda 2577-79, 2581-98, 2603-09

Dowell Az. as follows:

Ft. Riley 2500 15%
Herington-Krdier 3000 15%
Winfield 2000 15%
Towanda 3000 15%
All zones 24,000 7 1/2%