


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

27-26-38W

Company - STANOLIND OIL AND GAS CO.
Farm - McMichael Gas Unit - No. 1

SEC. 27 T. 26. R. 38W
2490' S of N1 and 2490'
W of E1 of NE
SW SW NE

County. Kearney
KANSAS



Total Depth. 2618'
Comm. 5-30-48 Comp. 7-4-48
Shot or Treated. Acidized
Contractor.
Issued. 9-25-48

CASING:

10 3/4" 590' Cem w/375 Sx.
7" 2406' Cem w/850 Sx.
5 1/2" 2618'

Elevation. 3191.2nd

Production. 9,964,000 gas

Figures Indicate Bottom of Formations.

sand and gravel	215
shale and sand	390
lime, blue gumbo	500
gumbo, shale	550
red rock	782
sand and shale	1110
lime, shale & anhyd.	1262
shale, shells	1354
salt	1446
anhydrite	1780
redbed	1809
anhyd. lime, gyp	1914
lime, gyp	2026
lime	2240
lime, gyp	2305
lime R.T.D.	2440
red rock	2461
shale	2482
red rock	2508
red rock, shale	2521
shale	2552
red rock	2561
lime	2618
Ran Stand. Gamma Ray	2618'
total depth	2618'

Tops:

Herington-Krider	2406' to 2450
Winfield	2459 to 2491
Towanda	2521 to 2555
Ft. Riley	2570 to 2612

Acidization:

Dowell ACD all zones with
19,000 gal. 15%. 14,364
gal. flush. Max. Press. 200#.
Broke to Vac. time 13 min.
on acid. 9 min on water.