

## MID CONTINENT PETROLEUM CORPORATION

WELL RECORD

ADAM RISSE NO.2

E $\frac{1}{2}$  NE $\frac{1}{4}$  Sec.6-20S-10W, Rice County, Kansas  
 990' from North Line & 330' from West line  
 Drilling Commenced December 29, 1935; Completed January 23, 1936  
 Production: 665 bbls.

FORMATION RECORD

soil & clay	0	20
sand	20	60
shale	60	100
sand	100	120
shale	120	200
shale & shells	200	1520
lime	1520	1557
lime shells	1557	1757
lime	1757	1849
lime shells	1849	2162
lime	2162	2280
shale	2280	2385
broken lime	2385	2430
shale	2430	2685
lime	2685	2925
shale blue	2925	2965
lime white	2965	3233
conglomerate	3233	3278
shale green	3278	3285
shale black	3285	3288
Silicious Lime	3288	3315 T.D.

CASING RECORD

Size	Casing Spot	Cement
12 $\frac{1}{2}$ " 50#	190'	200 sacks
7" OD 24#	3288'	325 "